

UTAH OIL AND GAS CONSERVATION COMMISSION

REMARKS: WELL LOG ☒ ELECTRIC LOGS ☒ FILE ☒ WATER SANDS ☐ LOCATION INSPECTED ☐ SUB REPORT abd

DATE FILED 6-20-80

LAND: FEE & PATENTED STATE LEASE NO. ML-27450

PUBLIC LEASE NO.

INDIAN

DRILLING APPROVED: 6-30-80

SPUDDED IN

COMPLETED: PUT TO PRODUCING:

INITIAL PRODUCTION

GRAVITY A.P.I.

GOR

PRODUCING ZONES

TOTAL DEPTH

WELL ELEVATION

DATE ABANDONED Location Abandoned Well Never Drilled 4-14-81

FIELD: ~~CTR. CISCO AREA~~ 796 Greater Cisco

UNIT

COUNTY: GRAND

WELL NO. BOWERS STATE #1-25

API NO. 43-019-30662

LOCATION 3300' FT. FROM ~~XX~~ (S) LINE.

1980'

FT. FROM ~~XX~~ (W) LINE

SE NW

1/4 - 1/4 SEC 25

TWP.	RGE.	SEC.	OPERATOR	TWP.	RGE.	SEC.	OPERATOR
19S	23E	25	BOWERS OIL & GAS				

FILE NOTATIONS

1. In NID File ☒

2. In S R Sheet ☐

3. Top Pinned ☒

4. ☐

5. Fee Land ☐

Checked by Chief ☐

Copy NID to Field Office ☐

Approval Letter ☐

Disapproval Letter ☐

TECH DATA:

D. Completed ☐

NEW ☐

G. IS ☐

TA ☐

PA ☐

Location Inspected ☐

Bond released ☐

State of Fee Land ☐

LOGS FILED

on ☐

Mo ☐

E

E-I ☐

GR ☐

GR-N ☐

Micro ☐

Senio ☐

Others ☐

9-28-90
for

BOWERS OIL & GAS EXPLORATION INC.

P.O. Box 636
GRAND JUNCTION, CO. 81502
EUS: 303-245-1342
FES: 303-242-6311

RECEIVED
JUN 20 1980

June 18, 1980

DIVISION OF
OIL, GAS & MINING

Utah Oil and Gas Commission
1588 W.N. Temple
Salt Lake City, UT 84116


Attention: Mr. Mike Minder

RE: Bowers State Well #125

Dear Mike:

Enclosed in triplicate is an APD for the above captioned well. Attached to each copy is a surveyplat along with a map which shows all acreage encompassing lease #27450 on which this proposed well site is located (shaded in red).

Sincerely,


James E. Bowers
President

JEB:lam

Enclosures

6

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS, AND MINING

5. Lease Designation and Serial No.

ML-27450

6. If Indian, Allottee or Tribe Name

N/A

7. Unit Agreement Name

N/A

8. Farm or Lease Name

N/A

9. Well No.

Bowers State #1-25

10. Field and Pool, or Wildcat

Gr Cisco Area

11. Sec., T., R., M., or Blk.

Unnamed
and Survey or Area

Sec. 25, T19S, R23E,

12. County or Parish 13. State SLB&M

Grand, Utah

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

1a. Type of Work

DRILL ☒DEEPEN ☐PLUG BACK ☐

b. Type of Well

Oil
Well ☐Gas
Well ☒

Other

Single
Zone ☐Multiple
Zone ☐

2. Name of Operator

Bowers Oil & Gas Exploration, Inc.

3. Address of Operator

P.O. Box 636, Grand Junction, Colorado, 81502

4. Location of Well (Report location clearly and in accordance with any State requirements.)*

At surface 1980 ft. FWL, 3300 ft. FSL. (SENW)

At proposed prod. zone same as above

14. Distance in miles and direction from nearest town or post office*

12 miles north of Cisco, Utah

15. Distance from proposed*

location to nearest

property or lease line, ft.

(Also to nearest drlg. line, if any)

660 ft.

16. No. of acres in lease

2081

17. No. of acres assigned

to this well

160

18. Distance from proposed location*
to nearest well, drilling, completed,
or applied for, on this lease, ft.

8400 ft. (approx.) 2920'

19. Proposed depth

20. Rotary or cable tools

Rotary

21. Elevations (Show whether DF, RT, GR, etc.)

4772 GR

22. Approx. date work will start*

July 15, 1980

23.

PROPOSED CASING AND CEMENTING PROGRAM

Size of Hole	Size of Casing	Weight per Foot	Setting Depth	Quantity of Cement
11"	8-5/8"	20#	200'	65 sx. (Class B)
6-3/4" to top of Oak.	4 1/2"	9.5#	2920'	140 sx. (RFC)
6-1/4" from Oak. top to TD.				

Circ. To Surface

We propose to drill with an air/air mist system until excessive gas is found or until TD if excessive gas is not encountered. When we mud-up, we will use a 3% KCL drispact/gel program (8.5-9.0 ppg). We will run dual induction/laterolog and compensated neutron/density downhole logs. No cores or drillstem tests are contemplated.

We will use a Schaeffer BOP with Grants Rotating Head attached to 150 ft. of blowey line. The BOP will be tested by pressurizing up the hole with the air compressors prior to drilling out from under surface pipe.

RECEIVED
JUN 20 1980

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

DIVISION OF
OIL, GAS & MINING

Signed

James E. Bowers

Title

President

Date

6/17/80

(This space for Federal or State office use)

Permit No.

43-019-30662

Approval Date

6/30/80

Approved by

Title

Date


Conditions of approval, if any:

APPROVED BY THE DIVISION
OF OIL, GAS, AND MINING

*See Instructions On Reverse Side

DATE: 6-30-80

BY: M. J. Minder




SCALE: 1" = 1000'

BOWERS STATE 1-25

Located North 3300 feet from the South boundary and East 1980 feet from the West boundary of Section 25, T19S, R23E, SLB&M.

Elev. 4772

Grand County, Utah



SURVEYOR'S CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF

Udell S. Williams

UTAH R.L.S. NO. 2573



UDELL S. WILLIAMS


751 Rood Avenue
GRAND JUNCTION, COLORADO 81501

PLAT OF
PROPOSED LOCATION

BOWERS STATE 1-25
SE $\frac{1}{4}$ NW $\frac{1}{4}$ SECTION 25
T19S, R23E, SLB&M

SURVEYED BY: USW DATE: 6/6/80
DRAWN BY: USW DATE: 6/6/80





**** FILE NOTATIONS ****

DATE: June 23, 1980
Operator: Bowens Oil & Gas
Well No: Bowens State #1-25
Location: Sec. 25 T. 19S R. 23E County: Grand
File Prepared: ☐ Entered on N.I.D.: ☒
Card Indexed: ☐ Completion Sheet: ☐

☒ API Number 43-019-30662

CHECKED BY:

Geological Engineer: _____

Petroleum Engineer: H.S. Kinder 6-30-80

Director: _____

APPROVAL LETTER:

Bond Required: ☒ Survey Plat Required: ☐
Order No. 102-16B 11/15/80 O.K. Rule C-3 ☐
Rule C-3(c), Topographic Exception/company owns or controls acreage
within a 660' radius of proposed site ☐

Lease Designation State Plotted on Map ☒

Approval Letter Written ☒ vtm

#3

PI nl

June 30, 1980

Bowers Oil and Gas Exploration
P.O. Box 636
Grand Junction, Colorado 81502

Re: Well Bowers State #1-25
Sec. 25, T. 19S, R. 23E.,
Grand County, Utah

Insofar as this office is concerned, approval to drill the above referred to gas well is hereby granted in accordance with the Order issued in Cause No. 102-16B dated November 15, 1980.

Should you determine that it will be necessary to plug and abandon this well, you are hereby requested to immediately notify the following:

MICHAEL T. MINDER - Petroleum Engineer
Office: 533-5771
Home: 876-3001

Enclosed please find Form OGC-8-X, which is to be completed whether or not water sands (aquifers) are encountered during drilling. Your cooperation in completing this form will be appreciated.

Further, it is requested that this Division be notified within 24 hours after drilling operations commence, and that the drilling contractor and rig number be identified.

The API number assigned to this well is 43-019-30662.

Sincerely,

DIVISION OF OIL, GAS AND MINING

Michael T. Minder
Petroleum Engineer

/btm

cc: Donald Prince

April 7, 1981

Bowers Oil and Gas Exploration Inc.
P.O. Box 636
Grand Junction Colorado 81502

Re: Well No. Bowers Federal #2-25
Sec. 25, T. 19S. R. 23E.
Grand County, Utah

Re; Well No. Bowers State #1-25
Sec. 25, T. 19S. R. 23E.
Grand County, Utah

Gentlemen:


In reference to the above mentioned wells, considerable time has gone by since approval was obtained from this office.

This office has not recieved any notification of spudding. If you do not intend to drill these wells, please notify this Division. If spudding or any other actin~~ing~~ has taken place, please send necessary forms. If you plan on drilling this location at a later date, please notify as such.

Your prompt attention to the above will be greatly appreciated.

Very truly yours,

DIVISION OF OIL, GAS, AND MINING



SANDY BATES
CLERK-TYPIST

BOWERS OIL & GAS EXPLORATION INC.

P.O. Box 636

GRAND JUNCTION, CO. 81502

BUS: 303-245-1342

RES: 303-242-6311

April 14, 1981

LA

State of Utah
Department of Natural Resources
Division of Oil, Gas and Mining
1588 West North Temple
Salt Lake City, Utah 84116

RE: Well No. Bowers Federal #2-25
Sec. 25, T19S, R23E
Grand County, Utah

RE: Well No. Bowers State #1-25
Sec. 25, T19S, R23E
Grand County, Utah

Gentlemen:

In regard to your letter dated April 7, 1981, Well #2-25 will be spudded the last week of April 1981, while the #1-25 will not be drilled in the near future.

If you have any further questions, please do not hesitate to call.

Sincerely,

James E. Bowers

James E. Bowers
President

JEB:ddh

RECEIVED
APR 16 1981

DIVISION OF
OIL, GAS & MINING